Sl. No.	Description	Unit	Nos	L	B	D	Qty	Rate	Amount
18	Providing and fixing of 50mm GI union to the motor ((PWD SR 13-14, P.NO.XXXVIII GI FITTINGS TABLE)								
		No's	2	2.00			4.00	223.70	894.80
	Basic Rate	223.70	Nos						
19	Labour Charges for end connection (MR)								
		No's	2				2.00	400.00	800.00
20	Labour charges for erection of new /repaired submersible pumpset along with GI pipes (32/50mm) cable (new submersible pumpset if required will be supplied by the department free of cost and released pump set should be handed over to department) including transportation (each length = 6.00m) (P.No - 564, I.No - 3, BWSSB SR 13-14)								
		Per length	2	54.00			108.00	88.00	9504.00
	Basic Rate	88.00	Nos						
21	Erection of combined panel board meter board with all necessary materials and labour including providing CC 1:3:6 foundation bed etc,. Complete for basement out door type.								
		No's	2	1.00			2.00	475.00	950.00
22	Supplying and fixing miniature circuit breakers/isolators in existing MCB distribution boards using necessary fixing materials and wiring complete as required, 40 to 63 Amps DP (P.NO - 526, I.NO - 13D (a), BWSSB SR 13-14)								
		No's	2	1.00			2.00	880.00	1760.00
	Basic Rate	880.00	Nos						
23	Supplying and laying of L.T.U.G Cable having aluminiumconductor PVC insulated shethed galvanised steel wire/ steel tape armoured cable with PVC outer sheathing 1.1 KV class 4 core 16 sqmm cable (confirming to IS 1554) (P.NO - 553, I.NO - 10 (d), BWSSB SR 13-14)								
		Mtr	2	30.00			60.00	165.00	9900.00
	Basic Rate	165.00	mtr						
24	Digging of trenches of 0.6mm x 0.50 Mtrs wide refilling the trench to the required ground level and consolidating etc,. Complete sutting road surfaces (P.NO - 554, I.NO - 12 (b), BWSSB SR 13-14)								
		Mtr	2	30.00			60.00	55.00	3300.00
	Basic Rate	55.00	mtr						
25	Supplying and fixing Class-A GI Pipe on pole/ wall/drain crossing with necessary clamping arrangements for UG Cable of 1.1 KV class 40mm (P.NO - 555, I.NO - 15 (b), BWSSB SR 13-14)								
		Mtr	2	2.00			4.00	286.00	1144.00
	Basic Rate	286.00	mtr						